REGISTERED POST



F.No. 17(6) P&F of Vitrified floor tile at VPM /AINP on VPM/18-19/Adm.V



Dated: 29.11.2018

To,

M/S	
JODHPUR.	

Sub: Quotation for providing and fixing of vitrified floor tile, wall panelling with anti-termite treatment of museum at VPM Building at ICAR- CAZRI, Jodhpur.

Dear Sir(s),

You are requested to kindly quote your lowest rates keeping in view the following conditions in respect of the articles indicated overleaf/as per statement enclosed (Schedule to tender).

- 1. No advance payment will be made. However, the payment is normally made within 30 days from the date of receipt of Bill for execution the work **in good condition as per order**.
- 2. The quantity proposed in the quotation may be increased or decreased at the discretion of the authority while placing the order.
- 3. Quotation not found according to specification will be rejected/not considered.
- 4. The firm should also supply a copy of the authorized dealership certificate of the item, if applicable
- 5. Quotation should remain valid for 3 months from the date of quotation.
- 6. No. Form 'C' & 'D' for sales tax will be issued. Payment will be made at full rate, if applicable. However, the firm is required to produce the valid sales tax Registration No. The firm should also indicate PAN/TIN as per Income Tax Rules.
- 7. The Rates **should be clearly indicated in figure as well as in words**. While quoting the rates, it may be clearly indicated whether the items are inclusive or exclusive of ST, CST etc. in terms of percentage or in absolute term.
- 8. Works will have to be completed normally within 30 days from the date of issue of work order or as mentioned in the supply order unless such extension is allowed by the Institute **failing which suitable penalty as indicated in the work order will be imposed.**
- 9. Director, CAZRI, Jodhpur reserves the right to accept or reject any or all the quotation without assigning any reason.
- 10. All bids must be accompanied by a bid security / **EMD of Rs. 4000/-** of the estimated value of the cost, in the form of a Demand Draft of a scheduled commercial bank in India, in favour of **ICAR Unit-CAZRI**, **Jodhpur**. Without EMD quotation will not be considered.
- 11. The firm awarded the contract may/will have to furnish a performance security in the form of Bank Guarantee as per the proforma to be supplied along with work order or FDR pledged to "**ICAR Unit CAZRI, Jodhpur**" from a scheduled Commercial Banks for an amount which may vary from 5% to 10% of the value of the contract at the discretion of Director, which should remain valid for six months.
- 12. The quotation may be sent to the office by courier/Registered Post/Speed Post in sealed cover super scribed with providing and fixing of vitrified floor tile, wall panelling with anti-termite treatment of museum at VPM Building at ICAR- CAZRI, Jodhpur.
- 13. The quotation must be reached to this Office on or before **12.12.2018 at 3.00 PM** which it will not be considered. The quotation should be dropped in the Tender Box placed in the Adm.V.

Yours faithfully,

ASSISTANT ADMINISTRATIVE OFFICER (V)



भा. कृ. अनु. प. —केन्द्रीय शुष्क क्षेत्र अनुसंधान संस्थान ICAR - Central Arid Zone Research Institute जोधपुर (राजस्थान) 342 003 / Jodhpur (Rajasthan) 342 003 Website: www.cazri.res.in, Email: director.cazri@icar.gov.in Phone No. 0291 - 2786584(Dir.)/2786485(CAO)/2785981(AO) FAX: 0291 - 2788706(Dir.)/2786498(PME)



F.No. 17(6) P&F of Vitrified floor tile at VPM /AINP on VPM/18-19/Adm.V

Dated: 29.11.2018

<u>निविदा प्रपत्र</u>

(इस फार्म को निविदा प्रपत्र के साथ जमा कराना आवश्यक है)

निदेशक, केन्द्रीय शुष्क क्षेत्र अनुसंधान संस्थान, जोधपुर निम्नलिखित कार्य के लिए सीमित मोहरबन्द निविदाये आमंत्रित करते है।

1. कार्य का नाम : Providing and fixing of vitrified floor tile, wall panelling with anti-termite treatment of museum at VPM Building at ICAR-CAZRI, Jodhpur. निविदादाता फर्म का नाम/पूर्ण पता 2. ; ····· टेलीफोन / मोबाईल नम्बर 3. निविदादाता फर्म का : PAN No. 4. :GST/TIN No. बैंक का विवरण : बैंक का नाम..... 5. ः पता : बैंक का IFS Code : ः बैंक का खाता नम्बर : निविदा प्रपत्र की कीमत : रू. शून्य 6. : रू. 4000/- Demand Draft/Pay Order/Banker Cheque धरोहर (बयाना) राशि 7. ICAR Unit CAZRI, Jodhpur के पक्ष में देय हो। कार्य पूर्ण करने की अवधि : एक माह 8. निविदा जमा कराने की अंतिम तिथि : 12/12/2018 at 3.00 PM 9. 10. निविदा कार्य की विस्तृत सूचना काजरी की वेबसाईट http://www.cazri.res.in पर देखी जा सकती है।

11. निविदा प्रपत्र काजरी, जोधपुर की वेबसाईट से भी डाउनलोड किये जा सकते है।

SI. Code Description Qty Unit Rate Amount No No Dismantling tile work in floors and roofs laid in cement 1 15.23 mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm 15.23.1 75 Sam @..... Demolishing cement concrete manually/ by mechanical 2 means including disposal of material within 50 metres lead 15.2 as per direction of Engineer - in - charge. 1:4:8 or leaner mix 15.2.2 3.00 Cum. @..... Providing and laying in position cement concrete of 3 4.1 specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 4.1.3 2.00 Cum. @..... 40 mm nominal size). 11.41 Providing and laying polished vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption's less than 0.08% and conforming to IS : 15622 of approved make in all colours and shades, laid on 4 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc., complete. 11.41.2 Size of Tile 60x60 cm sqm @..... 35 9.18 Providing and fixing Pre-laminated flat pressed 3 layer (medium density) particle board or graded wood particle board IS: 3087 marked, with one side decorative and other side balancing lamination Grade I, Type II exterior grade IS 5 : 12823 marked, in shelves with screws and fittings wherever required, edges to be painted with polyurethane primer (fittings to be paid separately). 25 mm thick 9.18.2 60 sqm @..... Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, 6 fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. 10.16 Hot finished welded type tubes 200 kg @..... 10.16.1 Anti-termite treatment by drilling 12 mm. holes at walls & floors & their junctions, injecting chemicals CHLOROPHYROPHOS 20% solutions @ 1.00 liter or more per 7 400 @..... per holes and plugging the holes with white/gray cement hole morter to match existing floors (1 liter water with 150 ml EC 20% solution). Anti-termite treatment of doors, windows, palmets etc. by using CHLOROPHYROPHOS (Trishul 20% EC) and K. oil in ratio of part of trishul 20% EC and 19 part of K.oil by volume i.e. 1 Liter Trishul 20% EC 19 k.oil mix solution including drilling holes 6 mm. dia. @ 30 cm. c/c Approx. filling the per @..... solutation in the holes @ 0.5 Liter or more per holes and hole plugging the holes with white/gray cement morter to match the existing all lead, lift cartage labour & material of T&P etc. required including all incidental charges as complete job. 200 Total

Name of work:-Providing and Fixing of Vitrified floor tile, Wall Panelling with Anti- Termite treatment of Museum at VPM Building at ICAR-CAZRI, Jodhpur

(Rupees

..... only)